

CENDEK RAILINGS LTD. TEST REPORT

SCOPE OF WORK

REPORT OF CENDEK RAILINGS LTD. 8 FT. CENTURY COMPONENT PICKET FASCIA MOUNT RAILING SYSTEM TESTED IN ACCORDANCE WITH ASTM E935-21, STANDARD TEST METHODS FOR PERFORMANCE OF PERMANENT METAL RAILING SYSTEMS AND RAILS FOR BUILDINGS

REPORT NUMBER

105973968COQ-001A

TEST DATES

10/18/24

ISSUE DATE

11/04/24

PAGES

24

DOCUMENT CONTROL NUMBER

GFT-OP-10c (09/29/20) © 2020 INTERTEK





Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24

REPORT ISSUED TO

CENDEK RAILINGS LTD.9685 Agur Street
Summerland, BC, VOH 1Z2
Canada

SECTION 1

SCOPE

Intertek Building & Construction (B&C) was contracted by Cendek Railings Ltd., 9685 Agur Street, Summerland, BC, V0H 1Z2, Canada, to perform testing on the 8 ft. Century Component Picket Fascia Mount Railing System in accordance with ASTM E935-21, Standard Test Methods for Performance of Permanent Metal Railing Systems and Rails for Buildings. The scope of the testing as requested by Cendek Railings Ltd., was to assess the ability of the guard system to resist the load requirements of R301.5 of the 2024 IRC. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted at the Intertek test facility in Coquitlam, BC, Canada on October 18, 2024.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

For INTERTEK B&C:

COMPLETED			
BY:	Chris Chang, P.Eng.	REVIEWED BY:	Baldeep Sandhu
	Senior Technician –		Manager –
TITLE:	Building & Construction	TITLE:	Building & Construction
	Alm		8-
SIGNATURE:	EGBC Permit No.: 1000953	SIGNATURE:	
DATE:	11/04/24	DATE:	11/04/24

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

Version: 29 September 2020 Page 2 of 24 GFT-OP-10c



Telephone: 604-520-3321 Facsimile: 604-524-9186

www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24

SECTION 2

SUMMARY OF TEST RESULTS

SYSTEM DESCRIPTION	TEST	PASS/FAIL
8 ft. Century Component Picket Fascia Mount Railing	In-fill Load	Pass
	Horizontal – Mid-Span Concentrated Load	Pass
System	Horizontal – Adjacent to Post Concentrated Load	Pass
	Horizontal – Top of Post Concentrated Load	Pass

Refer to Appendix B for photos of testing.

Version: 29 September 2020 Page 3 of 24 GFT-OP-10c



Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24

SECTION 3

TEST METHOD

The guard specimen was evaluated in accordance with the following:

ASTM E935-21, Standard Test Methods for Performance of Permanent Metal Railing Systems and Rails for Buildings.

The required test loads were based on the Specified Loads per the following Building Code articles with the Safety Factors applied as indicated in this report.

2024 International Residential Code (IRC)

• R301.5 Live Load

SECTION 4

MATERIAL SOURCE

The client submitted the railing system to the Evaluation Center on September 19, 2024 (Coquitlam ID# VAN2409230952-001). The sample was received in good condition and was suitable for testing unless noted otherwise. The sample was not independently selected for testing.

Version: 29 September 2020 Page 4 of 24 GFT-OP-10c



Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24

SECTION 5

EQUIPMENT

Calibration of test equipment was performed by Intertek B&C in accordance with ISO 17025 requirements.

ASSET #	DESCRIPTION	MODEL	CAL DUE DATE
P60692	Artech 5k lb S-Type Load Cell	20210-5k	01/15/25
D7830	Extech Temperature and Humidity Logger	RH550	11/07/24
P60624	Extech Stopwatch	365515	12/15/24
52650	Mitutoyo 8 in. Digital Caliper	CD-8	06/28/25
P60494	Stanley Tape Measure	FatMax	10/19/24

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Chris Chang	Intertek B&C
Stanley Miguel	Intertek B&C

Note: The above observer(s) witnessed part of the test program.

Version: 29 September 2020 Page 5 of 24 GFT-OP-10c



Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24

SECTION 7

TESTING PROCEDURE

The evaluation was conducted in accordance with the testing procedures of ASTM E935-21, Standard Test Methods for Performance of Permanent Metal Railing Systems and Rails for Buildings. The test specimen was loaded at a rate to achieve the specified loads between 10 seconds and 5 minutes. The specified test loads were held for one minute before the load was released. Testing was conducted with reference to the specified load requirements of the following:

IN-FILL LOAD TEST

The in-fill load test was conducted in accordance with Section 1607.9.1.2 *Guard Component Loads* of the 2024 IBC and Table R301.5 *Minimum Uniformly Distributed Live Loads* of the 2024 IRC. Testing was conducted with reference to Section 4.5.1.2 *Guard System Component Loads* of ASCE/SEI 7-22, *Minimum Design Loads and Associated Criteria for Buildings and Other Structures* with a safety factor of 2.5. A load of 125 lbs was applied using a 1 square foot block normal to the in-fill. After release of the load, the system was evaluated for failure, any evidence of disengagements of any component and/or visible cracking from any component.

CONCENTRATED LOAD TEST

The concentrated load tests were conducted in accordance with Section 1607.9.1 *Concentrated Load* of the 2024 IBC and Table R301.5 *Minimum Uniformly Distributed Live Loads* of the 2024 IRC. Testing was conducted with reference to Section 4.5.1 *Loads on Handrail and Guardrail Systems* of ASCE/SEI 7-22, *Minimum Design Loads and Associated Criteria for Buildings and Other Structures* with a safety factor of 2.5. The top rail of the guardrail system was subjected to three (3) separate horizontal tests where a concentrated load of 500 lbs was applied:

- horizontally at the mid-span of the top rail,
- horizontally at the top rail adjacent to the post connection to verify the connection capacity, and
- horizontally at the top of the post.

After release of the load, the system was evaluated for failure, any evidence of disengagements of any component and/or visible cracking from any component.

Version: 29 September 2020 Page 6 of 24 GFT-OP-10c



Telephone: 604-520-3321 Facsimile: 604-524-9186

www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24

SECTION 8

TEST SPECIMEN DESCRIPTION

The sample was identified as the following:

TABLE 1. RAILING CONFIGURATION						
		PART DIM	ENSIONS	REPORTED		
PART NAME	QTY	LENGTH	WIDTH	HEIGHT	NOMINAL THICKNESS	MATERIAL
Post	2	42.25 in.	2.50 in.	2.50 in.	0.07 in.	6063-T5 Aluminum
Baseplate	2	4.00 in.	4.00 in.	0.25 in.	N/A	6063-T5 Aluminum
Fascia Bracket	2	5.29 in.	4.50 in.	7.00 in.	N/A	6063-T5 Aluminum
Top Rail	1	95.29 in.	2.36 in.	1.89 in.	0.07 in.	6063-T5 Aluminum
Bottom Rail	1	95.29 in.	1.32 in.	1.41 in.	0.07 in.	6063-T5 Aluminum
Infill - Picket	21	37.88 in.	0.63 in.	0.63 in.	0.05 in.	6063-T5 Aluminum
Support Leg	2	3.82 in.	1.25 in.	6.93 in.	0.19 in.	6063-T5 Aluminum

Note 1: For detailed drawings of the test samples and components, refer to Appendix C.

SECTION 9

TEST RESULTS

A full set of test results is included in Appendix A.



Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24

SECTION 10

CONCLUSION

Intertek Testing Services NA Ltd. (Intertek) has conducted testing for Cendek Railings Ltd. on the 8 ft. Century Component Picket Fascia Mount Railing System per ASTM E935-21, Standard Test Methods for Performance of Permanent Metal Railing Systems and Rails for Buildings. The scope of the testing as requested by Cendek Railings Ltd. was to assess the ability of the guard system to resist the loads as prescribed in the following building code articles:

2024 International Residential Code (IRC)

• R301.5 *Live Load*

The Cendek Railings Ltd. 8 ft. Century Component Picket Fascia Mount Railing System identified and evaluated in this report has met the load requirements of the above criteria. Overall compliance with the Building Codes must be evaluated and approved by the Engineer of Record and Authority Having Jurisdiction.

The conclusions of this test may not be used as part of the requirements for Intertek product certification. Authority to Mark must be issued for a product to become certified.

Version: 29 September 2020 Page 8 of 24 GFT-OP-10c



Report No.: 105973968COQ-001A

Date: 11/04/24

1500 Brigantine Drive Coquitlam, BC, V3K 7C1

Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

SECTION 11

APPENDIX A – TEST DATA (2 PAGES)

Version: 29 September 2020 Page 9 of 24 GFT-OP-10c





ľ	Company	Cendek Railings Ltd.	Technician(s)	Chris Chang / Stanley Miguel
I	Project No.	G105973968	Reviewer	Baldeep Sandhu
I	Models	Fascia Mount	Start/End Date	October 18, 2024
I	Product Name	8 ft. Century Component Picket	Sample ID	VAN2409230952-001
I	Standard	2024 IRC	<u> </u>	

Test Data Package

Table of Contents

Sheet	Page
Table of Contents (This Sheet)	1
8 ft. Century Component Picket - Fascia Mount	2



Test: Loads on Guards Project: G105973968 18-Oct-24 Eng/Tech: Chris Chang Date: Stanley Miguel
Reviewer: Coquitlam, BC, Canada Client: Cendek Railings Ltd.

8 ft. Century Component - Fascia Mount Product:

Post Spacing: 8.21 ft 2.50 m Height of Guard: 42.1 in 1070 mm

Opening in Guard: 3.88 in 98 mm (between pickets)

Method: ASTM E935-13e1, Standard Test Methods for Performance of Permanent Metal Railing Systems and Rails for Buildings

2024 International Residential Code (IRC)

Safety Factor:

Equipment: Artech 5000 lbf Load Cell (Intertek ID# P60692, cal due January 15, 2025)

Extech RH550 Temperature and Humidity Logger (Intertek ID# D7830, cal due November 7, 2024)

Stopwatch (Intertek ID# P60624, cal due December 15, 2024) Mitutoyo Digital Caliper (Intertek ID# 52650, cal due June 28, 2025) Stanley Tape Measure (Intertek ID# P60494, cal due October 19, 2024)

Time/Temp/RH: 9:05AM / 22.4°C / 48.1%

Direction	Test	Design Load (Inward/ Outward) (Ibf)	Factored Load	Calculated Moment (lbf-ft)	Equivalent Quarter- Point Load (lbf)	Required Proof Load (lbf)	Pass/Fail
	Individual Elements (over 12 in. x 12 in.) (most critical location)	50	125	-	-	125	Pass
Outward	Midspan Horizontal Concentrated Load	200	500	-	-	500	Pass
	Top Rail Adjacent to Connection Concentrated Load	200	500	-	-	500	Pass
	Top of Post	200	500	-	-	500	Pass

Direction	Test	Design Load (Inward/ Outward) (kN)	Factored Load	Calculated Moment (kNm)	Equivalent Quarter- Point Load (kN)	Required Proof Load (kN)	Pass/Fail
	Individual Elements (over 305 mm in. x 305 mm) (most critical location)	0.22	0.56	-	-	0.56	Pass
Outward	Midspan Horizontal Concentrated Load	0.89	2.22	-	-	2.22	Pass
	Top Rail Adjacent to Connection Concentrated Load	0.89	2.22	-	1	2.22	Pass
	Top of Post	0.89	2.22	-	-	2.22	Pass



Report No.: 105973968COQ-001A

Date: 11/04/24

1500 Brigantine Drive Coquitlam, BC, V3K 7C1

Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

SECTION 11

APPENDIX B - PHOTOS (2 PAGES)



Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24




Figure 1. In-fill Load Test




Figure 2. Horizontal – Mid-span of Top Rail Concentrated Load



Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

TEST REPORT FOR CENDEK RAILINGS LTD.

Report No.: 105973968COQ-001A

Date: 11/04/24



Figure 3. Horizontal – Adjacent to Post Connection Concentrated Load



Figure 4. Horizontal – Top of Post Concentrated Load

Version: 05/10/17 Page 14 of 24 GFT-OP-10c



Report No.: 105973968COQ-001A

Date: 11/04/24


1500 Brigantine Drive Coquitlam, BC, V3K 7C1


Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

SECTION 12

APPENDIX C – DRAWINGS (8 PAGES)

Version: 05/10/17 Page 15 of 24 GFT-OP-10c





Railings Ltd. CenDek

Test sample complies with these details.

Deviations are noted.

Stortok

Report #: 105973968COQ-001A

104/24 Tech: C.C.

Date: 1(/

PROPRIETARY AND CONFIDENTIAL
THE INCORMATION CONFAINED IN THIS
DEARWING IS THE SOLE PROPERTO OF CONFORMER ALIMS SUID. ANY REPRODUCTION IN PART
OR AS A WHOLE WITHOUT THE WITHIN PERMISSION
OF CANDER ALIMOST ID IS PROMISTED.

DESCRIPTION Century Top Rail Die

CREATED 11/3/2017 MATERIAL 6063-T5

DRAWN BY Admin


ALL DIMENSION IN INCHES/mm DIE NO. DYG12073190


0.77 Lbs

Eng No. 0041P SHEET 2 OF 2

INITIALS DATE REVISIONS DESCRIPTION

REV.





STORES

Test sample complies with these detalls. Deviations are noted.

Report #: 105973968 COQ-0014

Date: 11 (04/04) Tech: C.C.

CenDek Railings Ltd.

PROPRIETARY AND CONFIDENTIAL
THE INCOPARATION CONVAINED IN THS
DRAWING ISTHE SOLE PROPERTY OF
CENDER MAILINGS ILD. ANY REPRODUCTION IN PART
OF AS A WHOLE WHINGOIL THE WRITTED PERMISSION
OF CENDER RAILINGS ILD. SPECHIFIED.

INITIALS

DATE

REVISIONS DESCRIPTION

REV.


 DRAWN BY
 Admin
 DESCRIPTION


 CREATED
 11/6/2017
 2-1/2" Post Material 12"


 MATERIAL
 6063-T5


DIE NO. DYG12076190
ALL DIMENSION IN INCHES/mm Fart 110.

Part No. Weight 0.98 Lbs SHEET 2 OF 2











Report No.: 105973968COQ-001A

Date: 11/04/24

1500 Brigantine Drive Coquitlam, BC, V3K 7C1

Telephone: 604-520-3321 Facsimile: 604-524-9186 www.intertek.com

SECTION 13

REVISION LOG

REVISION #	DATE	PAGES	REVISION
0	11/04/24	N/A	Original Report Issue